

“DESIGN, MANUFACTURE, SUPPLY, INSTALLATION, TESTING AND COMMISSIONING OF TEN NUMBERS OF BOGIE TURN TABLES FOR AHMEDABAD METRO RAIL PROJECT PHASE-I”							ADDENDUM NO: 6, DATED: 20-03-2018
TENDER NOTIFICATION No: MEGA/GD & AD/MP-L7/2017 Dated: 20th Dec, 2017							TENDER No: MEGA/GD & AD/MP-L7/2017
Sr. No.	Volume No	Section	Page No.	Clause No / Appendix	Paragraph / Line	Clause Description (relevant portion) as existing in the Tender Documents	Clause Description (relevant portion) as amended now to be read as
1.	3	ER-TS	12 of 32	Clause 3	Sub Clause 3.3.2	<p>3.3 CONSTRUCTION OF BOGIE TURN TABLE:</p> <p>3.3.2 Two pairs of rails of specified gauge shall be mounted and positioned in perpendicular to each other across diameter on the deck of each Bogie Turn Table to accommodate bogies. The track gauge shall be 1435 mm or as specified for particular workshop site. The rail shall be 60 Kg (UIC) and mounted with 1:20 inwards slope (it will be confirmed at the time of design from Track Work Contractor/ Employer).</p>	<p>3.3 CONSTRUCTION OF BOGIE TURN TABLE:</p> <p>3.3.2 Two pairs of rails of specified gauge shall be mounted and positioned in perpendicular to each other across diameter on the deck of each Bogie Turn Table to accommodate bogies. The track gauge shall be 1435 mm or as specified for particular workshop site. The rail shall be 60 Kg (UIC) and mounted with 1:20 inwards slope (it will be confirmed at the time of design from Track Work Contractor/ Employer).</p> <p style="text-align: center;">OR</p> <p>Two pairs of rails of specified gauge shall be mounted and positioned in perpendicular to each other across diameter on the deck of each Bogie Turn Table to accommodate bogies. The track gauge shall be 1435 mm or as specified for particular workshop site. The track profile of supplied rails shall be similar to 60 Kg or 52 kg (UIC) profile rail and mounted with 1:20 inwards slope (it will be confirmed at the time of design from Track Work Contractor/ Employer). <i>In case, similar profile rails are used, additional onsite warranty of 2 years shall be applicable at no extra cost to the Purchaser.</i></p>
2.	3.	ER-TS	12 of 32	Clause 3	Sub Clause 3.4.3	<p>3.4 CONSTRUCTION OF PLATFORM:</p> <p>3.4.3 The Bogie Turn Table platform shall be covered with steel chequered plates and flush with the rail top level to allow normal traffic. The plates shall be stiffened and minimum 19 mm thick with maximum deflection not exceeding 1/1000 of the span. The plates shall be removable and fixed with flush bolts.</p>	<p>3.4 CONSTRUCTION OF PLATFORM:</p> <p>3.4.3 The Bogie Turn Table platform shall be covered with steel chequered plates and flush with the rail top level to allow normal traffic. The plates shall be stiffened and minimum 19 mm thick or combination of 2 plates of 10 mm thickness each, with maximum deflection not exceeding 1/1000 of the span. The plates shall be removable and fixed with flush bolts. <i>In case, 2 plates of 10 mm thickness are used, additional onsite warranty of 2 years shall be applicable at no extra cost to the Purchaser.</i></p>

Sd/- (Snehal Shah) Sr. DGM – Civil & Proc.	Sd/- (Amit Gupta) CGM - CP	Sd/- (Sahadeva Singh) Director –P&P	Sd/- (Biren Parmar) Director Finance	Sd/- (Dr. I. P. Gautam) Managing Director
--	----------------------------------	---	--	---