

“Construction of 4.4 KM Elevated Viaduct and 03 Nos Stations (Including E&M and Excluding Architectural, Finishing & Roofing) from Saroli Metro Station to Surat HSR Metro Station Under Corridor - II in Connection with Surat Metro Rail Project Phase – 1 Extension”

Tender No.GMRC/CONS/VDCT+STNS/SURAT/PH-1 EXT./2026					ADDENDUM NO: 1, DATED: 17-10-2026	
S. N.	Vol no.	Vol. name	Clause No.	Page no.	Clause Description (relevant portion) as existing in the Bid Documents	Clause Description (relevant portion) as amended now to be read as
1	1	ITT	F 5.1	25	The Performance Security required in accordance with Clause 4.2 of the GCC shall be for 5% of the Contract Price from the Scheduled commercial Bank in India in the currency in which the Contract Price is payable. The Performance Security shall be furnished to the Employer within 28 (Twenty eight) days of issue of the Letter of Acceptance.....	The Performance Security required in accordance with Clause 4.2 of the GCC shall be for 10% of the Contract Price from the Scheduled commercial Bank in India in the currency in which the Contract Price is payable. The Performance Security shall be furnished to the Employer within 30 (Thirty) days of issue of the Letter of Acceptance.....
2	2	SCC, Part B	13.3.1	-	New Clause Added	Subclause 13.3.1 Variation in the Bill of Quantities in GCC is replaced with the following entirely. Refer Annexure - 1 to Addendum no. 1 (The changes are highlighted in Red Font)
3	2	SCC	14.12	-	New Clause Added	Subclause 14.12 Discharge in GC is replaced with the following entirely. 14.12 Discharge - At the time of submission of the Final Statement, the Contractor shall also submit a discharge confirming that the amount stated in the Final Statement represents full and final settlement of all monies due to the Contractor under or in connection with the Contract. The Contractor shall further confirm the closure of all tax liabilities and import/customs duty obligations falling under its responsibility. The discharge may stipulate that it shall become effective upon receipt by the Contractor of the Performance Security and payment of the outstanding balance of the amount stated in the Final Statement. In such a case, the discharge shall become effective on the date on which the above conditions are fulfilled. The No Dues Certificate shall be submitted in the format prescribed in the specimen enclosed as an Annexure, duly notarized by a Notary Public.(Refer Annexure - 5 of Addendum no. 1)
4	2	SCC	14.2	29	14.2 Advance Payment	Subclause 14.2 Advance Payment is replaced with the following entirely. Refer Annexure - 2 to Addendum no. 1 (The changes are highlighted in Red Font)

S. N.	Vol no.	Vol. name	Clause No.	Page no.	Clause Description (relevant portion) as existing in the Bid Documents	Clause Description (relevant portion) as amended now to be read as
5	3	ER	Appendix 2A "Work Areas"	96	GMRC will provide approx. 6 hectare land within 25 Km radius of work site for establishing the casting yard.	GMRC will provide approx. 5 hectare land within 25 Km radius of work site for establishing the casting yard.
6	4	TS - Civil	APPROVED/ LIKELY MANUFACTURERS/SUPPLIERS, Table S.N 5	360	Approved Manufactures / Suppliers - Civil Works SN 5, Admixtures	Approved Manufactures / Suppliers - Civil Works SN 5, Admixtures M/s. Normate India Pvt. Ltd. is added.
7	4	TS - Civil	APPROVED/ LIKELY MANUFACTURERS/SUPPLIERS	362	Approved Manufactures / Suppliers - Civil Works SN 28, Aiquid polymer membrane waterproofing	Approved Manufactures / Suppliers - Civil Works SN 28, Aiquid polymer membrane waterproofing M/s. Normate India Pvt. Ltd. is added.
8	4	TS - Civil works	APPROVED/ LIKELY MANUFACTURERS/SUPPLIERS, Table S.N 28	363	Approved Manufactures / Suppliers - Civil Works SN 32, Testing labs	Approved Manufactures / Suppliers - Civil Works SN 32, Testing labs Metttest Engg Services LLP. is added.
9	5	Tender drawings	Tender drawings S.N 18, 19, 20, 21, 22, 23, 24, 25, 27, 28, 29	-	Tender drawings from S.N 18, 19, 20, 21, 22, 23, 24, 25, 27, 28, 29	Tender drawings from S.N 18, 19, 20, 21, 22, 23, 24, 25, 27, 28, 29 replaced as per Annexure - 3 of Addendum - 1
10	5	Tender drawings	-	-	-	E&M Drawings Refer Annexure - 4 to Addendum no. 1
11	6	BoQ	PREAMBLE , SN 5	2	5. The rates in BOQ are exclusive of GST (18%) and all other Taxes and cess, octroi etc. as on date of submission.	The rates in BOQ are exclusive of GST (18%) and custom duties but including all other Taxes and cess, octroi etc. as on date of submission.
12	6	BoQ	Note, 3	8	The bidder's quote to be filled in Annexure – 1 (i.e. Summary Sheet of Bill of Quantity), it should be exclusive of all taxes (GST & Custom duties).	The bidder's quote to be filled in Annexure – 1 (i.e. Summary Sheet of Bill of Quantity), it should be exclusive of GST & Custom duties.

S. N.	Vol no.	Vol. name	Clause No.	Page no.	Clause Description (relevant portion) as existing in the Bid Documents	Clause Description (relevant portion) as amended now to be read as																								
13	6	BoQ	Item no. 1	9	<table><tr><th>Item</th><th>Description</th><th>Unit</th><th>Rate</th><th>Quantity</th><th>Amount (Rs.)</th></tr><tr><td>1</td><td>Surveying for verifying alignment, marking pier location, vertical & horizontal clearances and establishing triangulation points and bench marks for the elevated corridor including corrections, if any.....</td><td>KM</td><td>3,648.50</td><td>4.4</td><td>3,68,053.40</td></tr></table>	Item	Description	Unit	Rate	Quantity	Amount (Rs.)	1	Surveying for verifying alignment, marking pier location, vertical & horizontal clearances and establishing triangulation points and bench marks for the elevated corridor including corrections, if any.....	KM	3,648.50	4.4	3,68,053.40	<table><tr><th>Item</th><th>Description</th><th>Unit</th><th>Rate</th><th>Quantity</th><th>Amount (Rs.)</th></tr><tr><td>1</td><td>Surveying for verifying alignment, marking pier location, vertical & horizontal clearances and establishing triangulation points and bench marks for the elevated corridor including corrections, if any.....</td><td>KM</td><td>83,648.50</td><td>4.4</td><td>3,68,053.40</td></tr></table>	Item	Description	Unit	Rate	Quantity	Amount (Rs.)	1	Surveying for verifying alignment, marking pier location, vertical & horizontal clearances and establishing triangulation points and bench marks for the elevated corridor including corrections, if any.....	KM	83,648.50	4.4	3,68,053.40
Item	Description	Unit	Rate	Quantity	Amount (Rs.)																									
1	Surveying for verifying alignment, marking pier location, vertical & horizontal clearances and establishing triangulation points and bench marks for the elevated corridor including corrections, if any.....	KM	3,648.50	4.4	3,68,053.40																									
Item	Description	Unit	Rate	Quantity	Amount (Rs.)																									
1	Surveying for verifying alignment, marking pier location, vertical & horizontal clearances and establishing triangulation points and bench marks for the elevated corridor including corrections, if any.....	KM	83,648.50	4.4	3,68,053.40																									
14	6	BOQ	Schedule B3 – Precast Concrete Work, Item no. 1a	29	A. Casting bed for U -girder - 36 nos. B. Casting bed for pier cap - 8 nos C. Casting bed for I girder - 6 nos. I Girder D. Batching plant capacity should be minimum 60 cum/hour & 30 cum/hour The payment of this item shall be made as under A. Developing access -10% B. Establishing bed for U girder, I girder, pier cap and gantries - 40%. C. Establishing of batching plant, labs, office - 30% D. Completion of full facilities as approved by engineer -20%. The amount shall be paid against the indemnity bond.	A. Casting bed for Box Girder - 3 nos. short bed and 3 nos. long bed B. Casting bed for I girder, pie-girder - As per requirement C. Casting bed for Pier-Arm, L-girder, T-girder - As per requirement D. The batching plant capacity should be minimum 1 no 60 cum/hour & 1 no 30 cum/hour The payment of this item shall be made as under A. Developing access -10% B. Establishing bed for Box, I girder, etc. and gantries - 40%. C. Establishing of batching plant, labs, office - 30% D. Completion of full facilities as approved by engineer -20%. The amount shall be paid against the indemnity bond.																								
15	6	BOQ	Schedule B3 – Precast Concrete Work, Item no. 18	36	Providing M40 grade reinforced cement concrete (as per technical specification) for concreting, curing, transporting, lifting, installing precast parapet over Deck slab on both side of viaduct , including transition span as per the drawing in all precast psc I-girder/steel girder spans (straight or curved), with all leads. The cost includes shuttering, scaffolding, special adjustable props for alignment of units, moulds, providing cut outs, bolts & inserts for fixing signalling mast, curing, required dosage of admixture for concrete, all handling, and fixing in position, etc. complete) with cast in situ stitch concrete of same grade.Note: Payment at 50% of accepted rate on casting and Balance 50% on completion of erection, stitch concrete and related works. Rate includes cost of providing grooves/logo of client if required (the ribs/grooves/logo in shutter if required, shall be as per drawing).	Providing M40 grade reinforced cement concrete (as per technical specification) for concreting, curing of precast parapet . The cost includes shuttering, scaffolding, special adjustable props for alignment of units, moulds, providing cut outs, bolts & inserts for fixing signalling mast, curing, required dosage of admixture for concrete, all handling, and fixing in position, etc. complete with cast in situ stitch concrete of same grade. Rate includes cost of providing grooves/logo of client if required (the ribs/grooves/logo in shutter if required, shall be as per drawing).																								
16	6	BOQ	Schedule B3 – Precast Concrete Work, Item no. 19	36	Transportation, erection and installation of precast parapets over already erected superstructure(psc i- girder/steel girder portion) conforming to required lines, grades and dimension complete as per drawings and specifications including cast in situ stitch concrete of same grade. The weight shall be calculated assuming concrete density of 2.5 t/m³. Shifting within the site/yard is the responsibility of the contractor and shall not be paid separately	Transportation, erection and installation of precast parapets over already erected superstructure(psc i- girder/steel girder portion) conforming to required lines, grades and dimension complete as per drawings and specifications. The weight shall be calculated assuming concrete density of 2.5 t/m³. Shifting within the site/yard is the responsibility of the contractor and shall not be paid separately																								