"Construction of 4.62 km Elevated Viaduct from Dudheshwar to Vadaj, including 3 Nos. Elevated Stations of Ahmedabad Metro Rail Project"

Tender No.GMRC/CONS/STNS+VDCT - 7/2026 | **ADDENDUM NO: 1, DATED: 19-11-2026**

S. N.	Vol. no.	Vol. name	Clause No.	Page no.	Clause Description (relevant portion) as existing in the Bid Documents	Clause Description (relevant portion) as amended now to be read as
1	1	NIT	1.1.2 (e)	3	(e)Tender documents on sale / download of Tender Documents = From 07-10-2026 to **21-11-2026** (up to 15:00 hrs) on e-tendering website https://tender.nprocure.com. Tender document can only be obtained online after registration of tenderer on the website https://tender.nprocure.com. For further information in this regard bidders are advised to Contact No. +91 79 23248572, Extension 526/527	(e)Tender documents on sale / download of Tender Documents = From 06-10-2026 to **03-12-2026** (up to 15:00 hrs) on e-tendering website https://tender.nprocure.com. Tender document can only be obtained online after registration of tenderer on the website https://tender.nprocure.com. For further information in this regard bidders are advised to Contact No. +91 79 23248572, Extension 526/527
2	1	NIT	1.1.2 (j)	3	(j) Last date and time of submission of E-Tender (Technical & Financial Bid online) = **21-11-2026,** 15:00 Hrs	(j) Last date and time of submission of E-Tender (Technical & Financial Bid online) = **03-12-2026**, 15:00 Hrs
3	1	NIT	1.1.3.2 (A1)	11	(A1). The tenderers will be qualified only if they have successfully completed work(s), completion date(s) of which falling during last seven years ending last day of the month previous to the month of tender submission as given below:	(A1). The tenderers will be qualified only if they have successfully completed work(s) as prime contractor**, completion date(s) of which falling during last seven years ending last day of the month previous to the month of tender submission as given below:

S. N.	Vol. no.	Vol. name	Clause No.	Page no.	Clause Description (relevant portion) as existing in the Bid Documents	Clause Description (relevant portion) as amended now to be read as
4	1	NIT	1.1.3.2 (A1)	11	An **additional paragraph** has been inserted below the definition of "Similar Works" to clarify the term "Prime Contractor" and further requirements.	**Prime Contractor shall mean a tenderer who has executed works directly as a contractor / sub-contractor***, and not merely as Project Implementation Agency (PIA), supplier either individually or as a part of JV/Consortium. Works executed as PIA, Employer's Representative (ER), Project Management Consultancy (PMC), or as a material supplier shall not be considered for Qualification. ***Sub Contractors shall be considered eligible only if the following conditions are satisfied for the similar works submitted by them: (i). They have been approved as a subcontractor by the employer of the main contractor for the work. A certificate in this regard from the employer of the main contractor should be submitted. AND (ii). They have done both the supply and execution work as a part of the scope of their work. A certificate from the employer of the main contractor issued directly to the subcontractor, stating that the works executed include both supply and execution work. This will be in addition to the submission of FOT in Appendix-17 which should be issued by the employer of the main contractor.

S. N.	Vol. no.	Vol. name	Clause No.	Page no.	Clause Description (relevant portion) as existing in the Bid Documents	Clause Description (relevant portion) as amended now to be read as
5	1	NIT			(A2) Specific Experience (E&M Experience) Fire Protection Works - Rs. 3.27 Crore …….In case, if bidder(s) doesn't possess the above specific experience on their own as mentioned in 1.1.3.2 (A2), they may propose designated sub-contractor(s), fulfilling the above criteria, with necessary details in the Appendix 17 of FOT. **The tenderer may propose minimum two sub-contractor (Maximum up to three) having the experience mentioned as above.** [i.e. 1.1.3.2 (A2)]. However, during the execution of work, the tenderer will obtain GMRC's approval while sub-contracting the above said works.....	(A2) Specific Experience (E&M Experience) Fire Protection Works - Rs. 3.26 Crore …….In case, if bidder(s) doesn't possess the above specific experience on their own as mentioned in 1.1.3.2 (A2), they may propose designated sub- contractor(s), fulfilling the above criteria, with necessary details in the Appendix 17 of FOT. The tenderer may propose sub-contractor (Maximum up to three) having the experience mentioned as above. [i.e. 1.1.3.2 (A2)]. However, during the execution of work, the tenderer will obtain GMRC's approval while sub-contracting the above said works.....
6	2	SCC, Part A	14.8	6	14.8 Publishing source of commercial interest rates for financial charges in case of delayed payment = **Deleted**	14.8 Delayed Payment / Publishing source of commercial interest rates for financial charges in case of delayed payment = Clause 14.8 is deleted
7	2	SCC, Part B	4.1	14	Insert the following at the end of the 2nd paragraph: "The Contractor commits to meet the GMRC's eligibility criteria as listed under Appendix C to the General Conditions."…….	The addition of 2nd paragraph in SCC is "Deleted"
8	2	SCC, Part B	20.6	-	New Clause Added	Refer Subclause 20.6 Conciliation in GC *Delete the last paragraph entirely and replace it by following* The Conciliation shall be undertaken in accordance with Clause 20.7 of GC. The Conciliator shall assist the parties to reach an amicable settlement in an independent and impartial manner.
9	2	SCC, Part B	8.7	25	8.7. Delay Damages	8.7. Delay Damages Refer Annexure - 1 of Addendum no. 1

S. N.	Vol. no.	Vol. name	Clause No.	Page no.	Clause Description (relevant portion) as existing in the Bid Documents	Clause Description (relevant portion) as amended now to be read as
10	2	SCC, Part B	14.12	-	New Clause Added	Subclause 14.12 Discharge in GC is replaced with the following entirely. 14.12 Discharge - At the time of submission of the Final Statement, the Contractor shall also submit a discharge confirming that the amount stated in the Final Statement represents full and final settlement of all monies due to the Contractor under or in connection with the Contract. The Contractor shall further confirm the closure of all tax liabilities and import/customs duty obligations falling under its responsibility.The discharge may stipulate that it shall become effective upon receipt by the Contractor of the Performance Security and payment of the outstanding balance of the amount stated in the Final Statement. In such a case, the discharge shall become effective on the date on which the above conditions are fulfilled. The No Dues Certificate shall be submitted in the format prescribed in the specimen enclosed as an Annexure, duly notarized by a Notary Public.(Refer Annexure - 2 of Addendum no. 1)
11	1	FoT	App. - 1, SN V	6	Clause 11 of the GCC = 'Defects Liability Period' for the whole of the Works = 52 weeks after the date of issue of Taking- Over Certificate for the Whole of the Works.	Clause 11 of the GCC = 'Defects Liability Period' for the whole of the Works = 52 weeks for Civil Works and 104 weeks for E&M Works after the date of issue of Taking- Over Certificate for the Whole of the Works.
12	2	SCC, Part A	1.1.3.7	4	1.1.3.7 Defects Notification Period / Defects Liability Period (DLP) = 52 weeks after the date of issue of Taking- Over Certificate for the Whole of the Works.	1.1.3.7 Defects Notification Period / Defects Liability Period (DLP) = 52 weeks for Civil Works and 104 weeks for E&M Works after the date of issue of Taking- Over Certificate for the Whole of the Works.

S. N.	Vol. no.	Vol. name	Clause No.	Page no.	Clause Description (relevant portion) as existing in the Bid Documents	Clause Description (relevant portion) as amended now to be read as
13	2	SCC, Part B	14.2	29	14.2 Advance Payment Add this after Recovery of advances a. in GC Sub clause 14.2 with provisions as under a.1 No advance shall be given after 40% of the Original Contract Amount has been paid	14.2 Advance Payment Add this after Recovery of advances a. in GC Sub clause 14.2 with provisions as under a.1 No advance shall be given after 40% of the Original Contract Amount has been paid Advance Against Plant and Machinary …….The value of Bank Guarantee taken towards Security of "Plant & Machinery Advance" shall be 110% of the Advance taken by the Contractor and shall be in the form annexed to the Contract Data or in another form approved by the Employer.....
14	2	SHE Manual	-	-	VOLUME - 2, Condition of Contract on Safety & Health & Environment	VOLUME - 2 , Revised _ Condition of Contract on Safety & Health & Environment *(The changes can be seen in yellow colour / red font)* Refer Annexure - 3 of Addendum no. 1
15	3	Employer's Requirement	Appendix 2A - Works Areas	87	GMRC will provide approx. 6 hectare land within 25 Km radius of work site for establishing the casting yard. The contractor is solely responsible to establish the casting yard, batching plant, fabrication yard, work areas, offices etc. and other facilities without any liability and/ or additional cost to the Employer. Casting yard layout is to be developed by the contractor as per the land provided by the GMRC, in line with the DWP prepared by the contractor and as approved by the Employer/Engineer.	GMRC will provide approx. 6 hectare land within 30 Km radius of work site for establishing the casting yard. The contractor is solely responsible to establish the casting yard, batching plant, fabrication yard, work areas, offices etc. and other facilities without any liability and/ or additional cost to the Employer. Casting yard layout is to be developed by the contractor as per the land provided by the GMRC, in line with the DWP prepared by the contractor and as approved by the Employer/Engineer.

S. N.	Vol. no.	Vol. name	Clause No.	Page no.	Clause Description (relevant portion) as existing in the Bid Documents	Clause Description (relevant portion) as amended now to be read as
16	3	Employer's Requirement - Functional	2(i)	13	The work involves "Construction of 4.62 km Elevated Viaduct from Dudheshwar station to Vadaj station, including 03 Nos. elevated Stations viz. Dudheshwar, Sardar Colony and Vadaj station, including E&M Works for Ahmedabad Metro Rail Project, Phase-3C". This tender is for construction of elevated Viaduct structure mainly consisting of simply supported precast post-tensioned Box girder/I-girder/pie-girder spans on piers with pile foundations and on road/off road elevated Metro Stations comprising of pile foundation, pile cap, structural Frame comprising pier/portals, pier-Arms, pie-girders, T-girders, L-girders, beam, slab. The work also includes River bridge, existing Railway line crossing at one location and existing flyover crossing at two locations, Block works and Plaster work for the stations, and E&M	The work involves "Construction of 4.62 km Elevated Viaduct from Arihant Nagar station (excl.) to Vadaj station (incl.), including 03 nos. of elevated Stations viz. Dudheshwar, Sardar Colony and Vadaj station, including E&M Works for Ahmedabad Metro Rail Project, Phase-3C". This tender is for construction of elevated Viaduct structure mainly consisting of simply supported precast post-tensioned Box girder/I-girder/pie-girder spans on piers with pile foundations and on road/off road elevated Metro Stations comprising of pile foundation, pile cap, structural Frame comprising pier/portals, pier-Arms, pie-girders, T-girders, L-girders, beam, slab. The work also includes River bridge, existing Railway line crossing at one location and existing flyover crossing at two locations, Block works and Plaster work for the stations, and E&M Works.
17	4	TS - Civil	APPROVED/ LIKELY MANUFACTURERS/SUPPLIERS, Table S.N 2	360	Approved Manufactures / Suppliers - Civil Works SN 2, Reimforcement Bars	Approved Manufactures / Suppliers - Civil Works SN 2, Reimforcement Bars M/s. Gallantt Ispat Ltd. is added.
18	4	TS - Civil	APPROVED/ LIKELY MANUFACTURERS/SUPPLIERS, Table S.N 6	360	Approved Manufactures / Suppliers - Civil Works SN 6, Pile Integrity Testing Agency	Approved Manufactures / Suppliers - Civil Works SN 6, Pile Integrity Testing Agency M/s. RJ Metalab LLP is added

S. N.	Vol. no.	Vol. name	Clause No.	Page no.	Clause Description (relevant portion) as existing in the Bid Documents	Clause Description (relevant portion) as amended now to be read as
19	4	TS - Civil	APPROVED/ LIKELY MANUFACTURERS/SUPPLIERS, Table S.N 7	360	Approved Manufactures / Suppliers - Civil Works SN 7, Pile load testing	Approved Manufactures / Suppliers - Civil Works SN 7, Pile load testing M/s. RJ Metalab LLP is added
20	4	TS - Civil works	APPROVED/ LIKELY MANUFACTURERS/SUPPLIERS, Table S.N 32	363	Approved Manufactures / Suppliers - Civil Works SN 32, Testing labs	Approved Manufactures / Suppliers - Civil Works SN 32, Testing labs RJ Metalab LLP is added Metalab Analytical Pvt. Ltd. is added
21	6	BOQ	Schedule B3 Item No:18	42	Providing M40 grade reinforced cement concrete (as per techinical specification) for concreting, curing, transporting, lifting, installing precast parapet over Deck slab on both side of viaduct, including transition span as per the drawing in all precast psc I-girder/steel girder spans (straight or curved), with all leads. The cost includes shuttering, scaffolding, special adjustable props for alignment of units, moulds, providing cut outs, bolts & inserts for fixing signalling mast, curing, required dosage of admixture for concrete, all handling, and fixing in position, etc. complete) with cast in situ stitch concrete of same grade.Note: Payment at 50% of accepted rate on casting and Balance 50% on completion of erection, stitch concrete and related works. Rate includes cost of providing grooves/logo of client if required (the ribs/grooves/logo in shutter if required, shall be as per drawing).Minimum cement content shall be 390 kg/cum of concrete.	Providing M40 grade reinforced cement concrete (as per techinical specification) for concreting, curing of precast parapet. The cost includes shuttering, scaffolding, special adjustable props for alignment of units, moulds, providing cut outs, bolts & inserts for fixing signalling mast, curing, required dosage of admixture for concrete, all handling, and fixing in position, etc. complete with cast in situ stitch concrete of same grade. Note: Payment at 70% of accepted rate on casting and Balance 30% on completion of erection, stitch concrete and related works. Rate includes cost of providing grooves/logo of client if required (the ribs/grooves/logo in shutter if required, shall be as per drawing). Minimum cement content shall be 390 kg/cum of concrete.

S. N.	Vol. no.	Vol. name	Clause No.	Page no.	Clause Description (relevant portion) as existing in the Bid Documents	Clause Description (relevant portion) as amended now to be read as
22	10	BOQ	Sch-C-2,1.1E	117 of 149	Nicl. Batteries & Battery Charger.	VRLA maintenance free Batteries & Battery Charger
23	8.2	TS-E&M	TS-EM-1,EM-2,EM-3	All	Standard reffered in tender documents - NBC (2016)	Standard to be reffered in tender documents as- NBCS (2026)
24	8.2	TS-E&M	TS-EM-1	20 of 377	FRLSH -Fire Retardant Low Smoke Zero Halogen	To be read as FRLSH -Fire Retardant Low Smoke and Halogen
25	8.2	TS-E&M	TS-EM-1, 1.26,C	34 of 377	Contractor shall, within 90 days from completion of the work, provide a list of recommended spare parts required for the 36 months of service beyond the DLP/Maintenance period.	Contractor shall, within 90 days from completion of the work, provide a list of recommended spare parts required for the 60 months of service beyond the DLP/Maintenance period.
26	8.2	TS-E&M	TS-EM-3, Appendix 4	367 of 377	MAINTENANCE REQUIREMENTS	To be reffered as attached annexure Refer Annexure - 4 of Addendum no. 1
27	2	SCC, Part B	8.7	25	New Clause Added	13.8 Adjustments for Changes in costs Addition of Price Variation Formula for E&M Items Refer Annexure - 5 of Addendum no. 1

S. N.	Vol. no.	Vol. name	Clause No.	Page no.	Clause Description (relevant portion) as existing in the Bid Documents	Clause Description (relevant portion) as amended now to be read as
28	2	SCC, Part B	4.2	15	New Clause Added	13.8 Adjustments for Changes in costs The following para is added under Sub-clause 4.2, Performance Security (a) The successful bidder will be required to submit the Performance Security of 10% of the Contract Price excluding the amount of Comprehensive Annual Maintenance amount after issuance of Letter of Acceptance. The Performance Guarantee should be valid for a period of six months beyond the completion period + DLP period. (i.e. Completion period + Defect Liability Period + 6 months). (b) In addition, the successful bidder shall submit a separate Performance Security of 10% of Comprehensive Annual Maintenance value (CAMC) before the expiry of DLP period. The CAMC Performance Guarantee should be valid for a period of six months beyond the CAMC period of five (5) years.
29	3	ER	2.4.2	65	2.4 TRAFFIC MANAGEMENT 2.4.2 Traffic barricade with blinker, reflective tapes, traffic signage's, traffic sign board, signals, road delineator reflective lights, traffic cones, deployment of adequate man power for 8hrs, shift day and night management and other necessary provision should be provide wherever required so that safety is ensured during day and night continuously. Temporary traffic diversion for smooth flow of traffic during construction including necessary traffic signs, repairs to the diverted routes/service lanes, if required, restoration of diverted route to original condition etc, **shall be done by the Contractor at his cost.**	2.4.2 Traffic barricade with blinker, reflective tapes, traffic signage's, traffic sign board, signals, road delineator reflective lights, traffic cones, deployment of adequate man power for 8 hrs, shift day and night management and other necessary provision should be provide wherever required so that safety is ensured during day and night continuously. Temporary traffic diversion for smooth flow of traffic during construction including necessary traffic signs, repairs to the diverted routes/service lanes, if required, restoration of diverted route to original condition etc.